

- DO NOT INSTALL THE CHILLER OUTDOORS OR IN A LOCATION WHERE THE TEMPERATURE MAY FALL BELOW 32°F.
  WHEN INSTALLING CHILLER IN A CABINET, MAKE SURE THERE IS A VENT FOR AIR CIRCULATION OR AN OPENING IN CABINET BACK.
- 3. KEEP CHILLER AT LEAST 2 INCHES AWAY FROM CABINET WALL.
- 4. AFTER ALL CONNECTIONS ARE COMPLETE, OPEN FAUCET TO FLUSH CHILLER, TANK, TUBING & FILTER (IF USED). CHECK FOR LEAKS.
- 5. PLUG IN CHILLER AND ALLOW TO RUN UNTIL IT STOPS (APPROXIMATELY 7 TO 12 MINUTES).
- 6. WATER IS NOW CHILLED AND READY FOR DRINKING.

MT670-2 CHILLER SPECIFICATIONS	
POWER RATING	115V 60 Hz
POWER USAGE	75W (0.2 kw.hr/24hr), 1.2A
COMPRESSOR	SINGLE PHASE
REFRIGERANT	R134A, 1.2oz CHARGE
OUTPUT TEMP RANGE	39.2° F to 50° F
TANK CAPACITY	0.5 GALLONS
OUTPUT CAPACITY	3 GALLONS/HR
DIMENSIONS	10 1/8" HI, 11 3/4" DP, 16" WIDE
CERTIFICATIONS	C-UL-US, CB, WRAS
WARRANTY	THREE YEARS ON COMPRESSOR

